

Brad Constant Construction
16380 BOWMAN RD
COTTONWOOD ,CA 96022

Date	6/14/2023
------	-----------

Estimate

Estimate #
2023-45

Phone #	530-347-0445 /530- 339-6215
E-mail	bconstant76@yahoo.com
D I R #	1000013058

CSLB 793241

Name / Address
Anderson - Cottonwood Irrigation District 2810 Silver St. Anderson , Ca. 96007

Project	Location
Wet Wells	Hill Street

Item	Description	Qty	Rate	Total
03 Excavat...	Install wet well along the A.C.I.D. canal off of Hill Street. Excavate 36 inch hole , 10 feet deep and place 18 " perforated pipe in hole and surround with 1 1/2 " leach rock. Contractor will dewater and keep pipe clean of dirt and debris until all rock is placed. Contractor will cover top of pipe with modified cap for safety.	1	5,000.00	5,000.00

Thank you for the opportunity to serve you.	Total
---	--------------

\$5,000.00



A.C.I.D BID

Hill St. Sump Pump Pipe Installation

Pipe rock and labor included. The job will be completed to engineer specifications.

**Our equipment is low impact machinery with minimal disturbance to the soil.*

***A change order will be provided for any unforeseen extras.*

****A.C.I.D. to supply pump and generator for each hole.*

Bid Total: \$5000.00 per hole



Hill street pump pipe installation

Schuppert Excavating

Jschuppert12@gmail.com
4500 Webb Rd.
Anderson, CA, 96007
(530)604-9500
1011554

Billing address

Steve

Item	Description	Rate	Qty	Amount
Sump pump pipe instillation	Auger down and install pipe and rock per engineers specifications. Price is per hole.	5000.00	1	\$5,000.00

Total \$5,000.00

Thank you
Jason Schuppert